

This contract involved the construction of the Ballyshannon Sewerage Scheme which included 17km of new pipework in the town of Ballyshannon. The new pipes were laid in busy streets while maintaining traffic flow. A new pumping station was constructed to a depth of 8m on the shore of the Erne estuary under tidal conditions. The contract also required a crossing of the Abbey River. Significant quantities of hard rock were broken out in confined trenches. The contract required significant measures to maintain pedestrian access and traffic flow. Noise and vibration levels were monitored closely throughout the duration of the contract.



Ballyshannon Sewerage Scheme

Client – Donegal City Council

Engineer – J B Barry & Partners

Construction Period – 30th April 2007 - 09 January 2009

Value - €6.5 Million